
Typical R.C. Base Construction - Elevation



IN-SITU CONCRETE

- 1. REFER TO CCS CONSULTING IN-SITU CONCRETE SPECIFICATION 12. PENETRATIONS LESS THAN 300mm SQUARE OR DIAMETER ARE FOR ALL RELEVANT NOTES.
- CONCRETE GRADE FOR ALL OTHER ELEMENTS UNO C32/40
- 2. ALL CONCRETE TO BE STANDARD RC35 MIX TO BS8110: MIN CEMENT CONTENT 300kg/m³ OPC; MAX FREE WATER / CEMENT RATIO 0.6, MAX AGGREGATE SIZE 20mm & 5% AIR ENTRAINMENT.
- 3. ALL DIMENSIONS TO SLAB EDGE TO BE CONFIRMED BY THE ARCHITECT.
- 4. UNO CONCRETE COVER TO OUTERMOST REINFORCEMENT TO
- FOUNDATIONS 40mm BOTTOM, 40mm SIDE AND TOP
- 4. THE ABOVE COVERS RELATE TO CONCRETE CAST AGAINST FORMED SURFACES. WHERE CONCRETE IS CAST AGAINST NON-AGGRESSIVE SOIL, THE COVER TO REINFORCEMENT SHALL 16. ALL REINFORCEMENT TO BE GRADE 500 CONFORMING TO BS BE INCREASED TO 75mm.
- 5. ALL CONCRETE FACES TO BE CAST AGAINST FORMWORK UNLESS PRIOR CONSENT IS GRANTED BY THE ENGINEER.
- 6. ANY FORMWORK OR TEMPORARY PROPPING REQUIRED TO BE DESIGNED AND INSTALLED BY THE MAIN CONTRACTOR. DETAILS TO BE ISSUED TO CCS FOR COMMENT PRIOR COMMENCEMENT.
- 7. REFER TO ARCHITECTS DRAWINGS FOR DETAILS OF REBATES, CHAMFERS, ETC TO EXPOSED CONCRETE CONSTRUCTION.
- 8. 25x25 FILLETS TO BE INSTALLED TO ALL EDGES.
- 9. 100mm TROWELLED VERGE TO ALL EDGES AND BRUSHED FINISH 19. SIZE OF CONCRETE ELEMENTS DO NOT INCLUDE THICKNESS OF TO ALL HORIZONTAL SURFACES.
- 10. THE EXPOSED FACES OF THE CONCRETE STRUCTURES ARE TO BE INSPECTED IN ACCORDANCE WITH THE CCS CONSULTING IN-SITU CONCRETE SPECIFICATION. EXPOSED CONCRETE TO FOLLOW ARCHITECTURAL REQUIREMENTS WITH RESPECT TO FINISH, TEXTURE AND COLOUR.

NOT SHOWN ON THE STRUCTURAL DRAWINGS - REFER TO

DRAWINGS SHALL BE SUBMITTED TO THE ENGINEER FOR

13. WHERE REQUIRED PENETRATIONS OF THIS SIZE SHOULD BE

14. CONSTRUCTION JOINT POSITIONS OTHER THAN THOSE

15. MAXIMUM LENGTH OF TIME BEFORE POURING AGAINST

PREVIOUS DAYS WORK IS 4 DAYS.

CEMENT: SAND MIX WELL RAMMED IN.

DISPLACED TO SUIT.

ADJACENT POUR.

FORMED PRIOR TO POURING AND REINFORCEMENT LOCALLY

DETAILED ON THE DRAWINGS ARE TO BE AGREED WITH THE

ENGINEER IN ADVANCE OF CONSTRUCTION. THE JOINTS

SHOULD BE CLEANED AND ALL LOOSE CONCRETE / DEBRIS

REMOVED AND ROUGHENED PRIOR TO CONCRETING THE

4449:2005 AND SCHEDULED IN ACCORDANCE WITH BS 8666:2005

CORRECT POSITION DURING CONCRETING BY APPROVED BAR

17. ALL REINFORCEMENT SHALL BE SECURELY SUPPORTED IN ITS

CHAIRS, SPACERS OR SUPPORT BARS. THESE TEMPORARY

ELEMENTS WILL NOT BE SHOWN ON CCS CONSULTING

- IF THIS DRAWING HAS BEEN RECEIVED ELECTRONICALLY IT IS THE RECIPIENTS RESPONSIBILTY TO PRINT THE DOCUMENT TO THE CORRECT SCALE BUILDERS WORK DRAWINGS FOR DETAILS. BUILDINGS WORK
 - ALL DIMENSIONS ARE IN MILLIMETRES UNLESS STATED
 - THIS DRAWING SHOULD BE READ IN CONJUNCTION WITH ALL OTHER RELEVANT DRAWINGS AND SPECIFICATIONS
 - ANY DISCREPANCIES NOTED ON SITE ARE TO BE REPORTED TO THE ENGINEER IMMEDIATELY.

Legend

notes:

Denotes Propsoed (Min.) 800mm Wide Access Walkway


Denotes Outline of Existing Car Park Boundary/ Kerb Line

REINFORCEMENT DRAWINGS. 18. SURFACE HOLES RESULTING FROM THE USE OF FORMWORK THROUGH TIES SHALL BE PLUGGED WITH A SEMI-DRY 1:3

APPLIED FINISHES.

20. NO HOLES, CHASES OR EMBEDMENT OF PIPES OTHER THAN THOSE SHOWN ON THE STRUCTURAL DRAWINGS SHALL BE MADE IN CONCRETE MEMBERS WITHOUT THE PRIOR APPROVAL OF THE ENGINEER.

21. THE CONTRACTOR SHALL PROVIDE INFORMATION OF THEIR METHODS OF CONTROLLING THE CURING OF CONCRETE AND SHALL DETAIL THESE IN A METHOD STATEMENT FOR SUBMISSION TO THE ENGINEER/ARCHITECT IN ACCORDANCE WITH THE SPECIFICATION.



P1	Preliminary Issue	19.01.22	JF	WFF
T1	Tender Issue	10.02.22	JF	WFF

Manchester University NHS Foundation Trust

APPOINTED PARTY LOGO/INFORMATION



Costing

For

Wythenshawe Hospital -CSB Switchboard Replacement

Clinical Science Building -Proposed Switch Rooms & Generators Plan -(Option 02)

PURPOSE OF ISSUE For Tender D2

DRAWN BY CHECKED BY Jan. '22

PROJECT NUMBER SCALE (@A1) 21-2127 As Shown

FILE DRAWING NUMBER 212127 - CCS - D2 - XX- DR - S - 0410